

Maera



MAERA

**Apexindo first submersible swamp barge, built in 1992, added cantilever in 2003 and last dry dock in 2018.
10,000 Psi BOP System – 7,500 Psi WP Mud Pump – 3,000 HP Drawwork**

Design : APEXINDO / Protomac 7 to 25 ft water depth; 25,000 ft drilling
Gross Tonnage / LOA : 3,735 Ton / 68.89 m
Power : 4 x Caterpillar D-3516 - 1,580 HP each
SCR : Ross Hill
Mast : Pyramid 1,650,000 lbs GNC
Drawworks : Gardner Denver 3,000 HP
Mud Pumps : 3 x Gardner Denver PZL 1,600 HP 7,500 Psi WP
Rotary table : Gardner Denver RT 375. 37½" opening. 550 ton.
Top Drive : Varco TDS-4S high torque
Solid Control : 4 x VSM 300 Shale Shakers - Brandt
1 x SRS-3 desander
1 x SE-16 desilter
1 x VG-I degasser
2 x FVSD HS 3400 centrifuges - Brandt
Mud Pits : 400 m3 liquid
Bulk Storage : 3,000 cuft cement; 3,000 cuft barite / bentonite
BOP Equipment : 29 1/2" x 500 Psi Diverter – Hydril
13 5/8" x 5,000 Psi Annular - Cameron
13 5/8" x 10,000 Psi 4 rams – Cameron
Cantilever : Lateral 2 x 12 ft; longitudinal 22 ft
Cranes : 2 x BMC 900 100 ft boom max hoist 49,965 lbs @20 ft
Living Quarters : 100 persons; 2 beds in clinic

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 Jl. Jend. Sudirman Kav. 52-53 , Jakarta 12190
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111
Email: info@apexindo.com
Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788
Contact Person : Donald Kent Wood (Director/ Independent Director)

www.apexindo.com