



## RIG #14

Rated Drill Depth : 8,000 ft  
Rig Type : Mobile Land  
Drawworks : Skytop Brewster RR-850 DH 800 HP  
Mast : Telescopic Skytop Brewster 410,000 lbs GNC (10 lines) 115 ft  
Substructure : 388,000 GNC x 17.6 ft of high (RT-GL), 14.2 ft (Below RT-GL)  
Capable to perform workover/completion on geothermal well by using additional pony sub to elevate rotary table 24 ft above GL, 20.6 ft (Below RT-GL)  
Engines : 2 unit GM 12V-71, 400 HP each (one unit for back up)  
Generators : 3 x CAT D379 - 600 KW each  
SCR System : Mud pumps, Drawwork is driven directly by each engine c/w MCC Electric Panel Shack  
Rotary Table : 27 1/2" maximum table opening  
Hoisting Equipment : Travelling Block, IDECO MFC, 250 tons  
Pumps : 3 Unit Triplex Pump 8P-80 Model, 800 HP driven by CAT D-398  
BOP EQUIPMENT : 21 1/4"- 2,000 psi annular  
13 5/8"- 5,000 psi annular  
13 5/8" – 5,000 psi two (2) single RAM  
Mud Tank Capacity : 900 bbls capacity  
Solid Control : 2 Unit Shale Shaker.  
Manufacture by MI-Swaco.  
Model Mongoose, Provide with 2 Vibrator Motor.  
Capable of Handling 10.0 ppg of mud.  
16 ea 4" cones desilter  
2 ea 10" cones dessander  
1 unit Degasser, Manufacture by MI-Swaco  
Drill Pipe : 4 1/2" Drill Pipe and 3 1/2" Drill Pipe  
Camp : 120 persons  
Transportation : 2 x CAT 950 Forklift  
1 x Oilfield Winch Truck

**2010 – Fully recondition and rebuilt to full standard of OEM**

### PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 JL. Jend. Sudirman Kav. 52-53 , Jakarta 12190  
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111  
Email: [info@apexindo.com](mailto:info@apexindo.com)

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114  
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

**[www.apexindo.com](http://www.apexindo.com)**