



RIG #10

Rated Drill Depth	: 20,000 ft
Draw works	: Ideco E-2100 2,000 HP
Mast	: Ideco, Cantilever 1,000,000 lbs GNC 142 ft Hook Load Capacity 12 Lines : 1.000.000 lbs Hook Load Capacity 10 Lines : 960.000 lbs
Substructure	: Ideco, Sling-shot Casing Load Rating : 1.000.000 lbs Set Back Capacity : 600,000 lbs
Engines	: 4 x Cat D-399TA 1,350 HP each + 1 x Cat D-399TA 1,350 HP for Independent Mud Pump
Generators	: 4 x AC 930 KW each + 1 x AC 930 KW for Independent Mud Pump
SCR System	: General Electric
Rotary Table	: 37 ½" opening independent drive
Hoisting Equipment	: 500 Tons
Top Drive	: Tesco HCIS 500/650 T 1205 HP c/w CAT 3512
Pumps	: 3 x Ideco T-1300 1,300 HP each + 1 x Independent Mud Pump Ideco T-1300 1,300 HP
BOP Equipment	: 29 1/2" x 500 psi Diverter system (1 unit) 21 1/4" x 2,000 psi Single ram (2 unit) 21 1/4" x 2,000 psi Annular (1 unit) 13 5/8" x 5,000 psi Single ram (1 unit) 13 5/8" x 5,000 psi Double ram (1 unit) 13 5/8" x 5,000 psi Annular (1 unit)
Mud Tank System	: 2,990 bbl system (Active Tank 1,172 bbl + Reserve Tank 1,818 bbl)
Solid Control	: 4 x derrick 514 shale shaker Mud cleaner 16 x cones desilter, 2 x cones desander
Drill Pipe	: 5" Drill pipe; 3 ½" Drill pipe
Camp	: Basecamp and Minicamp = 200 persons
Transportation	: 2 x 50 ton Crawler Crane 2 x 5 ton Forklift Cat 950

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 JL. Jend. Sudirman Kav. 52-53 , Jakarta 12190
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111
Email: info@apexindo.com

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

Contact Person : Donald Kent Wood (Director/ Independent Director)

www.apexindo.com