



RIG #4

Rated Drill Depth	: 15,000 ft
Drawworks	: Inter American Oil Works Inc / OWI I500
Mast	: Skytop Brewster / SB142-750, 1,000,000 lbs, 142 ft Mast Height
Substructure	: Skytop Brewster 500,000 lbs setback Capacity Box to Box / Skidding System
Engines	: 4 x Caterpillar 3512B, 1877 HP @1200 Rpm
Generators	: 4 x Caterpillar - SR 4B, 1400 KW (1200 rpm)
SCR System	: 5 Bay SCR - M&I Electric /1612
Rotary Table	: National C-375 650T, Max Opening 37 ½ inch
Hoisting Equipment	: Crown Block : Skytop Brewster 500 ton Traveling Block : Gardner Denver 550 ton
Top Drive	: 500T
Pumps	: 3 x Gardner Denver PZ-11 Mud Pumps 1,600 HP Each with 2 x 1,000 HP DC Motors
BOP Equipment	: 29 ½" x 500 psi Diverter 21-1/4" x 2,000 psi Annular 21.1/4" x 2,000 psi Single / Double Ram 13.5/8" x 5,000 psi Annular 13.5/8" x 5,000 psi Single / Double Ram
Mud Tank System	: 2000 bbl system / Brandt Mud Agitators
Solid Control	: 4 x Derrick Flowline Cleaner Shale Shakers; 12 x Cones Desilter / Mud Cleaner Swaco; 2 x Cones Dessander Swaco
Drill Pipe	: 5" NC50 Drill Pipe / 3-1/2" NC38 Drill Pipe
Camp	: 200 Man Base Camp + Rig Site Mini Camp
Warehouse	: 2x40' Containers + 8x20' Containers w/ Office

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 Jl. Jend. Sudirman Kav. 52-53 , Jakarta 12190
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111
Email: info@apexindo.com

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

Contact Person : Donald Kent Wood (Director/ Independent Director)

www.apexindo.com