



RIG #9

Rated Drill Depth	:	20,000 ft
Draw works	:	Gardner Denver 1500-E 2,000 HP
Mast	:	Lee C Moore, 1,300,000 lbs, Height 142 ft
Substructure	:	Lee C Moore / Self Elevating
Engines	:	4 x Caterpillar D399, 1,350 HP each
Generators	:	4 x Kato / SR 4, 1,050 KW each
SCR System	:	General Electric Generation 4 th
Rotary Table	:	Ideco 375, Max Opening independent drive 37-1/2", 650 Ton, 350 rpm.
Clear height below RT Beam to GL	:	29 ft
Hoisting Equipment	:	500 Tons
Top Drive	:	500 Tons
Pumps	:	3 x Gardner Denver PZ-10, 1,350 hp each
BOP Equipment	:	29 1/2" x 500 psi Diverter 21-1/4" x 2,000 psi Annular 21.1/4" x 2,000 psi Single / Double Ram 13.5/8" x 5,000 psi Annular 13.5/8" x 5,000 psi Single / Double Ram
Mud Tank System	:	1,800 bbl System
Solid Control	:	4 x Derrick FLC 514 shale shaker Mi Swaco / Mongoose PT-13 Mud Cleaner 20 x cones Desilter 3 x cones Dessander
Drill Pipe	:	5" NC50 Drill Pipe / 3-1/2" NC38 Drill Pipe
Camp	:	160 Man Base Camp + Rig Site Mini Camp
Warehouse	:	2 x 40' Containers + 8 x 20' Containers w/ Office

PT Apexindo Pratama Duta Tbk

Head Office : Office 8 20th – 21st Floor, SCBD Lot 28 Jl. Jend. Sudirman Kav. 52-53 , Jakarta 12190
Tel. (62-21)29333000 , 29333020 (Hunting) Fax. (62-21) 29333111
Email: info@apexindo.com

Branch Office : Jl. Jend. Sudirman, Balikpapan Permai Complex, Blok L No. 10-12, Balikpapan 76114
Tel. (62-542) 410 258 (Hunting) Fax. (62-542) 411 788

Contact Person : Donald Kent Wood (Director/ Independent Director)

www.apexindo.com